


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING					FORM 3 AMENDED REPORT <input type="checkbox"/>	
APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER Greater Monument Butte M-24-8-17		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT MONUMENT BUTTE		
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)		
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY				7. OPERATOR PHONE 435 646-4825		
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052				9. OPERATOR E-MAIL mcrozier@newfield.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-45431		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	1226 FNL 1912 FWL	SEnw	24	8.0 S	17.0 E	S
Top of Uppermost Producing Zone	1655 FNL 2554 FWL	SEnw	24	8.0 S	17.0 E	S
At Total Depth	2497 FSL 2363 FEL	NWSE	24	8.0 S	17.0 E	S
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 1043		23. NUMBER OF ACRES IN DRILLING UNIT 20		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 633		26. PROPOSED DEPTH MD: 6679 TVD: 6679		
27. ELEVATION - GROUND LEVEL 4995		28. BOND NUMBER WYB000493		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478		
ATTACHMENTS						
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES						
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER			<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN			
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)			<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER			
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)			<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP			
NAME Mandie Crozier		TITLE Regulatory Tech		PHONE 435 646-4825		
SIGNATURE		DATE 12/08/2010		EMAIL mcrozier@newfield.com		
API NUMBER ASSIGNED 43047514000000		APPROVAL  Permit Manager				

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	5.5	0	6679		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	6679	15.5			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	8.625	0	300		
Pipe	Grade	Length	Weight			
	Grade J-55 ST&C	300	24.0			

NEWFIELD PRODUCTION COMPANY
GREATER MONUMENT BUTTE M-24-8-17
AT SURFACE: SE/NW (LOT #3) SECTION 24, T8S, R17E
UINTAH COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1805'
Green River	1805'
Wasatch	6515'
Proposed TD	6679'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1805' – 6515'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. **Casing Design: Greater Monument Butte M-24-8-17**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950 17.53	1,370 14.35	244,000 33.89
Prod casing 5-1/2"	0'	6,679'	15.5	J-55	LTC	4,810 2.26	4,040 1.90	217,000 2.10

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. **Cementing Design: Greater Monument Butte M-24-8-17**

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	300'	Class G w/ 2% CaCl	138 161	30%	15.8	1.17
Prod casing Lead	4,679'	Prem Lite II w/ 10% gel + 3% KCl	323 1054	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

- *Actual volume pumped will be 15% over the caliper log
- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
 - Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 350 feet will be drilled with an air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**


The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2011, and take approximately seven (7) days from spud to rig release.

T8S, R17E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY**

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are base on LOCATION: an N.G.S. OPUS Correction. LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

M-24-8-17
(Surface Location) NAD 83
 LATITUDE = 40° 06' 18.00"
 LONGITUDE = 109° 57' 26.86"


WELL LOCATION, M-24-8-17,
 LOCATED AS SHOWN IN THE SE 1/4
 NW 1/4 (LOT 3) OF SECTION 24,
 T8S, R17E, S.L.B.&M. UTAH
 COUNTY, UTAH.

TARGET BOTTOM HOLE, M-24-8-17,
 LOCATED AS SHOWN IN THE NW 1/4
 SE 1/4 OF SECTION 24, T8S, R17E,
 S.L.B.&M. UTAH COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. 189377



TRI STATE LAND SURVEYING & CONSULTING
 180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

DATE SURVEYED: 08-30-10	SURVEYED BY: D.G.
DATE DRAWN: 10-08-10	DRAWN BY: M.W.
REVISED:	SCALE: 1" = 1000'

Access Road Map



Legend

—○— Existing Road



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

H-24-8-17 (Proposed Well)
M-24-8-17 (Proposed Well)
6-24-8-17 (Existing Well)


SEC. 24, T8S, R17E, S.L.B.&M. Uintah County, UT.

DRAWN BY: C.H.M.
DATE: 10-09-2010
SCALE: 1:100,000

TOPOGRAPHIC MAP

SHEET

A



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


H-24-8-17 (Proposed Well)
M-24-8-17 (Proposed Well)
6-24-8-17 (Existing Well)
SEC. 24, T8S, R17E, S.L.B.&M. Uintah County, UT.

DRAWN BY: C.H.M.
DATE: 10-09-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

SHEET
B

Proposed Pipeline Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518




NEWFIELD EXPLORATION COMPANY


H-24-8-17 (Proposed Well)
M-24-8-17 (Proposed Well)
6-24-8-17 (Existing Well)
SEC. 24, T8S, R17E, S.L.B.&M. Uintah County, UT.

DRAWN BY: C.H.M.
DATE: 10-09-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

SHEET
C





Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

H-24-8-17 (Proposed Well)
M-24-8-17 (Proposed Well)
6-24-8-17 (Existing Well)

SEC. 24, T8S, R17E, S.L.B.&M. Uintah County, UT.

DRAWN BY: C.H.M.
DATE: 10-09-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

SHEET
D



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 24 T8S R17E
M-24-8-17**

Wellbore #1

Plan: Design #1

Standard Planning Report

08 October, 2010





PayZone Directional Services, LLC.
Planning Report



Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well M-24-8-17
Company:	NEWFIELD EXPLORATION	TVD Reference:	M-24-8-17 @ 5007.0ft (Original Well Elev)
Project:	USGS Myton SW (UT)	MD Reference:	M-24-8-17 @ 5007.0ft (Original Well Elev)
Site:	SECTION 24 T8S R17E	North Reference:	True
Well:	M-24-8-17	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 24 T8S R17E			
Site Position:		Northing:	7,209,800.00 ft	Latitude: 40° 6' 9.036 N
From:	Lat/Long	Easting:	2,072,800.00 ft	Longitude: 109° 57' 14.911 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence: 0.99 °

Well	M-24-8-17, SHL LAT: 40° 06' 18.00, LONG: -109° 57' 26.86			
Well Position	+N/-S	907.0 ft	Northing:	7,210,690.83 ft
	+E/-W	-928.4 ft	Easting:	2,071,856.08 ft
Position Uncertainty	0.0 ft		Wellhead Elevation:	5,007.0 ft
			Ground Level:	4,995.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/10/08	11.37	65.88	52,390

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	5,050.0	0.0	0.0	123.77

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,428.4	12.43	123.77	1,422.0	-49.7	74.4	1.50	1.50	0.00	123.77	
5,143.5	12.43	123.77	5,050.0	-494.1	738.9	0.00	0.00	0.00	0.00	M-24-8-17 TGT
6,679.5	12.43	123.77	6,550.0	-677.8	1,013.7	0.00	0.00	0.00	0.00	

NEWFIELD



PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well M-24-8-17
TVD Reference: M-24-8-17 @ 5007.0ft (Original Well Elev)
MD Reference: M-24-8-17 @ 5007.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	123.77	700.0	-0.7	1.1	1.3	1.50	1.50	0.00
800.0	3.00	123.77	799.9	-2.9	4.4	5.2	1.50	1.50	0.00
900.0	4.50	123.77	899.7	-6.5	9.8	11.8	1.50	1.50	0.00
1,000.0	6.00	123.77	999.3	-11.6	17.4	20.9	1.50	1.50	0.00
1,100.0	7.50	123.77	1,098.6	-18.2	27.2	32.7	1.50	1.50	0.00
1,200.0	9.00	123.77	1,197.5	-26.1	39.1	47.0	1.50	1.50	0.00
1,300.0	10.50	123.77	1,296.1	-35.6	53.2	64.0	1.50	1.50	0.00
1,400.0	12.00	123.77	1,394.2	-46.4	69.4	83.5	1.50	1.50	0.00
1,428.4	12.43	123.77	1,422.0	-49.7	74.4	89.5	1.50	1.50	0.00
1,500.0	12.43	123.77	1,491.8	-58.3	87.2	104.9	0.00	0.00	0.00
1,600.0	12.43	123.77	1,589.5	-70.3	105.1	126.4	0.00	0.00	0.00
1,700.0	12.43	123.77	1,687.2	-82.2	123.0	147.9	0.00	0.00	0.00
1,800.0	12.43	123.77	1,784.8	-94.2	140.9	169.4	0.00	0.00	0.00
1,900.0	12.43	123.77	1,882.5	-106.1	158.7	191.0	0.00	0.00	0.00
2,000.0	12.43	123.77	1,980.1	-118.1	176.6	212.5	0.00	0.00	0.00
2,100.0	12.43	123.77	2,077.8	-130.1	194.5	234.0	0.00	0.00	0.00
2,200.0	12.43	123.77	2,175.4	-142.0	212.4	255.5	0.00	0.00	0.00
2,300.0	12.43	123.77	2,273.1	-154.0	230.3	277.0	0.00	0.00	0.00
2,400.0	12.43	123.77	2,370.8	-166.0	248.2	298.6	0.00	0.00	0.00
2,500.0	12.43	123.77	2,468.4	-177.9	266.1	320.1	0.00	0.00	0.00
2,600.0	12.43	123.77	2,566.1	-189.9	284.0	341.6	0.00	0.00	0.00
2,700.0	12.43	123.77	2,663.7	-201.8	301.8	363.1	0.00	0.00	0.00
2,800.0	12.43	123.77	2,761.4	-213.8	319.7	384.6	0.00	0.00	0.00
2,900.0	12.43	123.77	2,859.0	-225.8	337.6	406.1	0.00	0.00	0.00
3,000.0	12.43	123.77	2,956.7	-237.7	355.5	427.7	0.00	0.00	0.00
3,100.0	12.43	123.77	3,054.4	-249.7	373.4	449.2	0.00	0.00	0.00
3,200.0	12.43	123.77	3,152.0	-261.6	391.3	470.7	0.00	0.00	0.00
3,300.0	12.43	123.77	3,249.7	-273.6	409.2	492.2	0.00	0.00	0.00
3,400.0	12.43	123.77	3,347.3	-285.6	427.1	513.7	0.00	0.00	0.00
3,500.0	12.43	123.77	3,445.0	-297.5	444.9	535.3	0.00	0.00	0.00
3,600.0	12.43	123.77	3,542.6	-309.5	462.8	556.8	0.00	0.00	0.00
3,700.0	12.43	123.77	3,640.3	-321.5	480.7	578.3	0.00	0.00	0.00
3,800.0	12.43	123.77	3,738.0	-333.4	498.6	599.8	0.00	0.00	0.00
3,900.0	12.43	123.77	3,835.6	-345.4	516.5	621.3	0.00	0.00	0.00
4,000.0	12.43	123.77	3,933.3	-357.3	534.4	642.9	0.00	0.00	0.00
4,100.0	12.43	123.77	4,030.9	-369.3	552.3	664.4	0.00	0.00	0.00
4,200.0	12.43	123.77	4,128.6	-381.3	570.2	685.9	0.00	0.00	0.00
4,300.0	12.43	123.77	4,226.2	-393.2	588.1	707.4	0.00	0.00	0.00
4,400.0	12.43	123.77	4,323.9	-405.2	605.9	728.9	0.00	0.00	0.00
4,500.0	12.43	123.77	4,421.6	-417.1	623.8	750.4	0.00	0.00	0.00
4,600.0	12.43	123.77	4,519.2	-429.1	641.7	772.0	0.00	0.00	0.00
4,700.0	12.43	123.77	4,616.9	-441.1	659.6	793.5	0.00	0.00	0.00
4,800.0	12.43	123.77	4,714.5	-453.0	677.5	815.0	0.00	0.00	0.00
4,900.0	12.43	123.77	4,812.2	-465.0	695.4	836.5	0.00	0.00	0.00
5,000.0	12.43	123.77	4,909.8	-476.9	713.3	858.0	0.00	0.00	0.00
5,100.0	12.43	123.77	5,007.5	-488.9	731.2	879.6	0.00	0.00	0.00
5,143.5	12.43	123.77	5,050.0	-494.1	738.9	888.9	0.00	0.00	0.00



PayZone Directional Services, LLC.
Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:

Well M-24-8-17
M-24-8-17 @ 5007.0ft (Original Well Elev)
M-24-8-17 @ 5007.0ft (Original Well Elev)
True
Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
M-24-8-17 TGT									
5,200.0	12.43	123.77	5,105.2	-500.9	749.0	901.1	0.00	0.00	0.00
5,300.0	12.43	123.77	5,202.8	-512.8	766.9	922.6	0.00	0.00	0.00
5,400.0	12.43	123.77	5,300.5	-524.8	784.8	944.1	0.00	0.00	0.00
5,500.0	12.43	123.77	5,398.1	-536.8	802.7	965.6	0.00	0.00	0.00
5,600.0	12.43	123.77	5,495.8	-548.7	820.6	987.1	0.00	0.00	0.00
5,700.0	12.43	123.77	5,593.5	-560.7	838.5	1,008.7	0.00	0.00	0.00
5,800.0	12.43	123.77	5,691.1	-572.6	856.4	1,030.2	0.00	0.00	0.00
5,900.0	12.43	123.77	5,788.8	-584.6	874.3	1,051.7	0.00	0.00	0.00
6,000.0	12.43	123.77	5,886.4	-596.6	892.1	1,073.2	0.00	0.00	0.00
6,100.0	12.43	123.77	5,984.1	-608.5	910.0	1,094.7	0.00	0.00	0.00
6,200.0	12.43	123.77	6,081.7	-620.5	927.9	1,116.3	0.00	0.00	0.00
6,300.0	12.43	123.77	6,179.4	-632.4	945.8	1,137.8	0.00	0.00	0.00
6,400.0	12.43	123.77	6,277.1	-644.4	963.7	1,159.3	0.00	0.00	0.00
6,500.0	12.43	123.77	6,374.7	-656.4	981.6	1,180.8	0.00	0.00	0.00
6,600.0	12.43	123.77	6,472.4	-668.3	999.5	1,202.3	0.00	0.00	0.00
6,679.5	12.43	123.77	6,550.0	-677.8	1,013.7	1,219.4	0.00	0.00	0.00

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
M-24-8-17 TGT - plan hits target - Circle (radius 75.0)	0.00	0.00	5,050.0	-494.1	738.9	7,210,209.53	2,072,603.43	40° 6' 13.116 N	109° 57' 17.350 W




Project: USGS Myton SW (UT)
 Site: SECTION 24 T8S R17E
 Well: M-24-8-17
 Wellbore: Wellbore #1
 Design: Design #1




Azimuths to True North
 Magnetic North: 11.37°

Magnetic Field
 Strength: 52389.8snT
 Dip Angle: 65.88°
 Date: 2010/10/08
 Model: IGRF2010

KOP @ 600'
 DOGLEG RATE 1.5 DEG/100'
 TARGET RADIUS IS 75'



Vertical Section at 123.77° (1500 ft/in)



West(-)/East(+) (300 ft/in)

WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
M-24-8-17 TGT	5050.0	-494.1	738.9	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1428.4	12.43	123.77	1422.0	-49.7	74.4	1.50	123.77	89.5	
4	5143.5	12.43	123.77	5050.0	-494.1	738.9	0.00	0.00	888.9	M-24-8-17 TGT
5	6679.5	12.43	123.77	6550.0	-677.8	1013.7	0.00	0.00	1219.4	



**NEWFIELD PRODUCTION COMPANY
GREATER MONUMENT BUTTE M-24-8-17
AT SURFACE: SE/NW (LOT #3) SECTION 24, T8S, R17E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site Greater Monument Butte M-24-8-17 located in the SE 1/4 NW 1/4 Section 24, T8S, R17E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly – 6.8 miles \pm to it's junction with an existing road to the east; proceed easterly - 3.0 miles \pm to it's junction with an existing road to the northeast; proceed northeasterly - 0.3 miles \pm to it's junction with an existing road to the southeast; proceed in a southeasterly direction - 2.6 miles \pm to it's junction with an existing road to the northeast; proceed in a northeasterly and then a northwesterly direction - 0.4 miles \pm to the existing 6-24-8-17 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 6-24-8-17 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 41-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Bureau of Land Management.

12. OTHER ADDITIONAL INFORMATION

The Archaeological Resource Surveys and Paleontological Resource Surveys for this area are attached. MOAC Report #02-63, 6/10/02 and MOAC Report #05-04, 1/7/05. Paleontological Resource Survey prepared by, Wade E. Miller, 5/4/02 and 3/8/05. See attached report cover pages, Exhibit "D".

Surface Flow Line

Newfield requests 1,793' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new wells, Newfield. **Refer to Topographic Map "D"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

Installation: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

Termination and Final Reclamation: After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Details of the On-Site Inspection

The proposed Greater Monument Butte M-24-8-17 was on-sited on 11/9/10. The following were present; Tim Eaton (Newfield Production), Christine Cimiluca (Bureau of Land Management), Suzanne Grayson (Bureau of Land Management), and Janna Simonsen (Bureau of Land Management). Weather conditions were clear and ground cover was 100% open.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the Greater Monument Butte M-24-8-17, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the

hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Greater Monument Butte M-24-8-17, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Tim Eaton

Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052

Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #M-24-8-17, Section 24, Township 8S, Range 17E: Lease UTU-45431 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

12/8/10
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

December 9, 2010

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2010 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2010 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50528	GMBU M-23-8-17	Sec 23 T08S R17E 1995 FSL 1996 FWL BHL Sec 23 T08S R17E 2236 FNL 2273 FEL
43-013-50529	GMBU R-23-8-17	Sec 23 T08S R17E 1975 FSL 1991 FWL BHL Sec 23 T08S R17E 1164 FSL 2506 FEL
43-013-50530	GMBU N-23-8-17	Sec 23 T08S R17E 1874 FSL 0723 FWL BHL Sec 23 T08S R17E 2606 FNL 1374 FWL
43-013-50531	GMBU Q-23-8-17	Sec 23 T08S R17E 1863 FSL 0704 FWL BHL Sec 23 T08S R17E 1014 FSL 1464 FWL
43-047-51399	GMBU H-24-8-17	Sec 24 T08S R17E 1217 FNL 1933 FWL BHL Sec 24 T08S R17E 0260 FNL 2541 FEL
43-047-51400	GMBU M-24-8-17	Sec 24 T08S R17E 1226 FNL 1912 FWL BHL Sec 24 T08S R17E 2497 FSL 2363 FEL
43-047-51401	GMBU B-25-8-17	Sec 24 T08S R17E 0643 FSL 0674 FEL BHL Sec 25 T08S R17E 0334 FNL 1483 FEL
43-013-50532	GMBU Q-30-8-17	Sec 30 T08S R17E 1978 FSL 1911 FWL BHL Sec 30 T08S R17E 1245 FSL 1200 FWL

API#	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50533	GMBU R-30-8-17	Sec 30 T08S R17E 1996 FSL 1923 FWL BHL Sec 30 T08S R17E 1239 FSL 2393 FEL
43-013-50534	GMBU I-1-9-16	Sec 01 T09S R16E 2136 FNL 1969 FEL BHL Sec 01 T09S R16E 1162 FNL 1294 FEL
43-013-50535	GMBU K-1-9-16	Sec 06 T09S R17E 1988 FNL 0583 FWL BHL Sec 01 T09S R16E 2387 FSL 0291 FEL
43-013-50536	GMBU L-1-9-16	Sec 01 T09S R16E 1973 FSL 1961 FEL BHL Sec 01 T09S R16E 2458 FNL 1122 FEL
43-013-50537	GMBU S-1-9-16	Sec 01 T09S R16E 1964 FSL 1942 FEL BHL Sec 01 T09S R16E 0999 FSL 1028 FEL
43-013-50538	GMBU S-10-9-16	Sec 10 T09S R16E 0598 FSL 1959 FEL BHL Sec 10 T09S R16E 1450 FSL 1170 FEL
43-013-50539	GMBU R-10-9-16	Sec 10 T09S R16E 0644 FSL 2017 FWL BHL Sec 10 T09S R16E 1417 FSL 2500 FEL
43-013-50540	GMBU C-15-9-16	Sec 10 T09S R16E 0624 FSL 2022 FWL BHL Sec 15 T09S R16E 0200 FNL 2508 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management, ou=Branch of Minerals,
email=Michael_Coulthard@blm.gov, c=US
Date: 2010.12.09 11:11:06 -0700

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:12-9-10



VIA ELECTRONIC DELIVERY

December 10, 2010

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
Greater Monument Butte M-24-8-17
Greater Monument Butte (Green River) Unit

Surface Hole: T8S-R17E Section 24: SENW (Lot #3) (UTU-45431)
1226' FNL 1912' FWL

At Target: T8S-R17E Section 24: NWSE (UTU-45431)
2497' FSL 2363' FEL

Uintah County, Utah

Dear Ms. Mason;

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 12/8/10, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink, appearing to read "Shane Gillespie".

Shane Gillespie
Land Associate

Form 3160-3
(August 2007)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER


FORM APPROVED
OMB No. 1004-0137
Expires July 31, 2010

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-45431
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name NA
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. Greater Monument Butte
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Greater Monument Butte M-24-8-17
3b. Phone No. (include area code) (435) 646-3721		9. API Well No.
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SE/NW (Lot #3) 1226' FNL 1912' FWL Sec. 24, T8S R17E (UTU-45431) At proposed prod. zone NW/SE 2497' FSL 2363' FEL Sec. 24, T8S R17E (UTU-45431)		10. Field and Pool, or Exploratory Monument Butte
14. Distance in miles and direction from nearest town or post office* Approximately 14.6 miles southeast of Myton, UT		11. Sec., T. R. M. or Blk. and Survey or Area Sec. 24, T8S R17E
15. Distance from proposed* location to nearest property or lease line, ft. Approx. 1043' f/lease, NA' f/unit (Also to nearest drig. unit line, if any)	16. No. of acres in lease 548.53	12. County or Parish Uintah
17. Spacing Unit dedicated to this well 20 Acres	18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 633'	13. State UT
19. Proposed Depth 6,679'	20. BLM/BIA Bond No. on file WYB000493	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4995' GL	22. Approximate date work will start* 1st Qtr. 2011	23. Estimated duration (7) days from SPUD to rig release

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed Typed) Mandie Crozier	Date 12/18/10
Title Regulatory Specialist		
Approved by (Signature)	Name (Printed Typed)	Date
Title Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

T8S, R17E, S.L.B.&M.

NEWFIELD EXPLORATION COMPANY



WELL LOCATION, M-24-8-17, LOCATED AS SHOWN IN THE SE 1/4 NW 1/4 (LOT 3) OF SECTION 24, T8S, R17E, S.L.B.&M. UINTAH COUNTY, UTAH.

TARGET BOTTOM HOLE, M-24-8-17, LOCATED AS SHOWN IN THE NW 1/4 SE 1/4 OF SECTION 24, T8S, R17E, S.L.B.&M. UINTAH COUNTY, UTAH.



- NOTES:**
1. Well footages are measured at right angles to the Section Lines.
 2. Bearings are based on Global Positioning Satellite observations.

THIS IS TO CERTIFY THAT THE ABOVE SET WAS PREPARED FROM FIELD NOTES OF A SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.




TRI STATE LAND SURVEYING & CONSULTING
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 08-30-10	SURVEYED BY: D.G.
DATE DRAWN: 10-08-10	DRAWN BY: M.W.
REVISED:	SCALE: 1" = 1000'

M-24-8-17
(Surface Location) **NAD 83**
LATITUDE = 40° 06' 18.00"
LONGITUDE = 109° 57' 26.86"

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV.; Elevations are base on LOCATION: an N.G.S. OPUS Correction. LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

H-24-8-17 (Proposed Well)
M-24-8-17 (Proposed Well)
6-24-8-17 (Existing Well)

SEC. 24, T8S, R17E, S.L.B.&M. Uintah County, UT.




DRAWN BY: C.H.M.
DATE: 10-09-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

**SHEET
B**

API Number: 4304751400
Well Name: Greater Monument Butte M-24-8-17
Township 08.0 S Range 17.0 E Section 24
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPAN

Map Prepared:
 Map Produced by Diana Mason



WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/8/2010

API NO. ASSIGNED: 43047514000000

WELL NAME: Greater Monument Butte M-24-8-17

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: SENW 24 080S 170E

Permit Tech Review: ☒

SURFACE: 1226 FNL 1912 FWL

Engineering Review: ☐

BOTTOM: 2497 FSL 2363 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.10595

LONGITUDE: -109.95708

UTM SURF EASTINGS: 588889.00

NORTHINGS: 4439828.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-45431

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ **PLAT**

☒ **Bond:** FEDERAL - WYB000493

☐ **Potash**

☐ **Oil Shale 190-5**

☐ **Oil Shale 190-3**

☐ **Oil Shale 190-13**

☒ **Water Permit:** 437478

☐ **RDCC Review:**

☐ **Fee Surface Agreement**

☐ **Intent to Commingle**

Commingle Approved

LOCATION AND SITING:

☐ **R649-2-3.**

Unit: GMBU (GRRV)

☐ **R649-3-2. General**

☐ **R649-3-3. Exception**

☒ **Drilling Unit**

Board Cause No: Cause 213-11


Effective Date: 11/30/2009

Siting: Suspends General Siting

☒ **R649-3-11. Directional Drill**

Comments: Presite Completed
IRR SEC:

Stipulations: 4 - Federal Approval - dmason
15 - Directional - dmason
27 - Other - bhill



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Greater Monument Butte M-24-8-17
API Well Number: 43047514000000
Lease Number: UTU-45431
Surface Owner: FEDERAL
Approval Date: 12/14/2010

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-45431
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GREATER MON BUTTE M-24-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1226 FNL 1912 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 24 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43047514000000
9. FIELD and POOL or WILDCAT: MONUMENT BUTTE		COUNTY: UINTAH
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/14/2011	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Newfield proposes to extend the Application for Permit to Drill this well for one year.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12/19/2011

By:

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A	DATE 12/12/2011	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047514000000

API: 43047514000000

Well Name: GREATER MON BUTTE M-24-8-17

Location: 1226 FNL 1912 FWL QTR SENW SEC 24 TWNP 080S RNG 170E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/14/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.


- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 12/12/2011

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

RECEIVED Dec. 12, 2011

<div>STATE OF UTAH</div> <div>DEPARTMENT OF NATURAL RESOURCES</div> <div>DIVISION OF OIL, GAS, AND MINING</div>		<div>FORM 9</div> <div>5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-45431</div>	
<div>SUNDRY NOTICES AND REPORTS ON WELLS</div> <div>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</div>		<div>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</div> <div>7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)</div>	
<div>1. TYPE OF WELL Oil Well</div>		<div>8. WELL NAME and NUMBER: GREATER MON BUTTE M-24-8-17</div>	
<div>2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY</div>		<div>9. API NUMBER: 43047514000000</div>	
<div>3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052</div>		<div>PHONE NUMBER: 435 646-4825 Ext</div>	
<div>9. FIELD and POOL or WILDCAT: MONUMENT BUTTE</div>			
<div>4. LOCATION OF WELL FOOTAGES AT SURFACE: 1226 FNL 1912 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 24 Township: 08.0S Range: 17.0E Meridian: S</div>		<div>COUNTY: UINTAH</div>	
		<div>STATE: UTAH</div>	
<div>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</div>			
<div>TYPE OF SUBMISSION</div>		<div>TYPE OF ACTION</div>	
<div><div><input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/14/2012</div><div><input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:</div><div><input type="checkbox"/> SPUD REPORT Date of Spud:</div><div><input type="checkbox"/> DRILLING REPORT Report Date:</div></div>		<div><div><input type="checkbox"/> ACIDIZE</div><div><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div><div><input type="checkbox"/> CHANGE WELL STATUS</div><div><input type="checkbox"/> DEEPEN</div><div><input type="checkbox"/> OPERATOR CHANGE</div><div><input type="checkbox"/> PRODUCTION START OR RESUME</div><div><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div><div><input type="checkbox"/> TUBING REPAIR</div><div><input type="checkbox"/> WATER SHUTOFF</div><div><input type="checkbox"/> WILDCAT WELL DETERMINATION</div></div> <div><div><input type="checkbox"/> ALTER CASING</div><div><input type="checkbox"/> CHANGE TUBING</div><div><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div><div><input type="checkbox"/> FRACTURE TREAT</div><div><input type="checkbox"/> PLUG AND ABANDON</div><div><input type="checkbox"/> RECLAMATION OF WELL SITE</div><div><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div><div><input type="checkbox"/> VENT OR FLARE</div><div><input type="checkbox"/> SI TA STATUS EXTENSION</div><div><input type="checkbox"/> OTHER</div></div> <div><div><input type="checkbox"/> CASING REPAIR</div><div><input type="checkbox"/> CHANGE WELL NAME</div><div><input type="checkbox"/> CONVERT WELL TYPE</div><div><input type="checkbox"/> NEW CONSTRUCTION</div><div><input type="checkbox"/> PLUG BACK</div><div><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div><div><input type="checkbox"/> TEMPORARY ABANDON</div><div><input type="checkbox"/> WATER DISPOSAL</div><div><input checked="" type="checkbox"/> APD EXTENSION</div></div> <div>OTHER: <input type="text"/></div>	
<div>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</div> <div>Newfield proposes to extend the Application for Permit to Drill this well.</div> <div>Approved by the Utah Division of Oil, Gas and Mining</div> <div>Date: November 27, 2012</div> <div>By: </div>			
<div>NAME (PLEASE PRINT)</div> <div>Mandie Crozier</div>		<div>PHONE NUMBER</div> <div>435 646-4825</div>	<div>TITLE</div> <div>Regulatory Tech</div>
<div>SIGNATURE</div> <div>N/A</div>		<div>DATE</div> <div>11/26/2012</div>	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047514000000

API: 43047514000000

Well Name: GREATER MON BUTTE M-24-8-17

Location: 1226 FNL 1912 FWL QTR SENW SEC 24 TWNP 080S RNG 170E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/14/2010

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/26/2012

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER



FORM APPROVED
OMB No. 1004-0137
Expires July 31, 2010

5. Lease Serial No. UTU-45431	
6. If Indian, Allottee or Tribe Name NA	
7. If Unit or CA Agreement, Name and No. Greater Monument Butte	
8. Lease Name and Well No. Greater Monument Butte M-24-8-17	
9. API Well No. 43-047-51400	
10. Field and Pool, or Exploratory Monument Butte	11. Sec., T. R. M. or Blk. and Survey or Area Sec. 24, T8S R17E
12. County or Parish Utah	13. State UT
14. Distance in miles and direction from nearest town or post office* Approximately 14.6 miles southeast of Myton, UT	
15. Distance from proposed* location to nearest property or lease line, ft. Approx. 1043' f/lse, NA' f/unit (Also to nearest drig, unit line, if any)	16. No. of acres in lease 548.53
17. Spacing Unit dedicated to this well 20 Acres	18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 633'
19. Proposed Depth 6,679'	20. BLM/BIA Bond No. on file WYB000493
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4995' GL	22. Approximate date work will start* 1st Qtr. 2011
23. Estimated duration (7) days from SPUD to rig release	
24. Attachments	

RECEIVED
JUN 25 2013

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 12/8/10
Title Regulatory Specialist		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date JUN 19 2013
Title Assistant Field Manager Lands & Mineral Resources		
Office VERNAL FIELD OFFICE		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

UDOGM

DEC 15 2010

NOS 115XS 0062A

AFMSS# 10-19-2010

BLMVERNAL,UTAH

CONDITIONS OF APPROVAL ATTACHED

NOTICE OF APPROVAL




UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Newfield Production Company
Well No: GMBU M-24-8-17
API No: 43-047-51400

Location: Lot 3, Sec. 24, T8S R17E
Lease No: UTU-45431
Agreement: Greater Monument Butte

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm ut vn opreport@blm.gov
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

Site Specific COA's

Minerals and Paleontology

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- A permitted paleontologist must be present to monitor any ground disturbing activities.

Green River District Reclamation Guidelines

The Operator will comply with the requirements of the ***Green River District (GRD) Reclamation Guidelines*** formalized by Green River District Instructional Memo UTG000-2011-003 on March 28, 2011. Documentation of the compliance will be as follows:

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that designates the proposed site-specific monitoring and reference sites chosen for the location. A description of the proposed sites shall be included, as well as a map showing the locations of the proposed sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3 growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed areas in order to determine whether the BLM standards set forth in the GRD Reclamation Guidelines have been met (30% or greater basal cover).
- Prior to beginning new surface disturbance, the operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) providing the results of the noxious weed inventory described in the GRD Reclamation Guidelines (2011). If weeds are found the report shall include 1) A GPS

location recorded in North American Datum 1983; 2) species; 3) canopy cover or number of plants; 4) and size of infestation (estimate square feet or acres. Information shall be also documented in the reclamation report.

CONDITIONS OF APPROVAL

Wildlife

In accordance with the Record of Decision for the Castle Peak and Eightmile Flat Oil and Gas Expansion Project, Newfield Rocky Mountains Inc., the following COA's are required:

- WFM-1 On level or gently sloping ground (5 percent slope or less) Newfield will elevate surface pipelines (4 inches or greater in diameter) a minimum of 6 inches above the ground to allow passage of small animals beneath the pipe. This ground clearance will be achieved by placing the pipeline on blocks at intervals of 150 to 200 feet.
- WFM-4 Newfield will install noise reduction devices on all pump jacks to reduce intermittent noise to 45 dBA at 660 feet from the source.

COA's derived from mitigating measures in the EA:

If construction and drilling is anticipated during any of the following wildlife seasonal spatial restrictions, a BLM biologist or a qualified consulting firm biologist must conduct applicable surveys using an accepted protocol prior to any ground disturbing activities.

- There is a ferruginous hawk nest within ½ mile of the proposed project area. If construction or drilling is proposed from March 1-August 31, then a nesting survey will be conducted by a qualified biologist according to protocol. If the nest is found to be inactive, then permission to proceed may be granted by the BLM Authorized Officer. If the nest is determined to be active, then the timing restriction will remain in effect.

For protection of T&E Fish if drawing water from the Green River

- For areas of fresh water collection, an infiltration gallery will be constructed in a Service approved location. An infiltration gallery is basically a pit or trench dug within the floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures above and the pump head will be located in the river channel where larval fish are known to occur, the following measures apply:
 - Avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fish
 - Avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (see previous bullet); and
 - Avoid pumping, to the greatest extent possible, during the midnight hours (10:00 p.m. to 2:00 a.m.) as larval drift studies indicate that this is a period of greatest daily activity. Dusk is the preferred pumping time, as larval drift abundance is lowest during this time.
 - Screen all pump intakes with 3/32-inch mesh material.

- Report any fish impinged on the intake screen to the FWS office (801.975.3330) and the:
Utah Division of Wildlife Resources
Northeastern Region
152 East 100 North
Vernal, UT 84078
(435) 781-9453

Air Quality

- All internal combustion equipment will be kept in good working order.
- Water or other approved dust suppressants will be used at construction sites and along roads, as determined appropriate by the Authorized Officer. Dust suppressant such as magnesium chloride or fresh water may be used, as needed, during the drilling phase.
- Open burning of garbage or refuse will not occur at well sites or other facilities.
- Drill rigs will be equipped with Tier II or better diesel engines.
- Low bleed pneumatics will be installed on separator dump valves and other controllers.
- During completion, no venting will occur, and flaring will be limited as much as possible. Production equipment and gathering lines will be installed as soon as possible.
- Telemetry will be installed to remotely monitor and control production.
- When feasible, two or more rigs (including drilling and completion rigs) will not be run simultaneously within 200 meters of each other. If two or more rigs must be run simultaneously within 200 meters of each other, then effective public health buffer zones out to 200 meters (m) from the nearest emission source will be implemented. Examples of an effective public health protection buffer zone include the demarcation of a public access exclusion zone by signage at intervals of every 250 feet that is visible from a distance of 125 feet during daylight hours, and a physical buffer such as active surveillance to ensure the property is not accessible by the public during drilling operations. Alternatively, the proponent may demonstrate compliance with the 1-hour NO₂ National Ambient Air Quality Standards (NAAQS) with appropriate and accepted near-field modeling. As part of this demonstration, the proponent may propose alternative mitigation that could include but is not limited to natural gas-fired drill rigs, installation of NO_x controls, time/use restrictions, and/or drill rig spacing.
- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horse power must not emit more than 2 grams of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower-hour.
- All new and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 grams of NO_x per horsepower-hour.
- Green completions will be used for all well completion activities where technically feasible.
- Employ enhanced VOC emission controls with 95% control efficiency on production equipment having a potential to emit greater than 5 tons per year.

Plants: Threatened, Endangered, Proposed, or Candidate

Discovery Stipulation: Reinitiation of Section 7 consultation with the USFWS will be sought immediately if any loss of plants or occupied habitat for Pariette cactus or Uinta Basin hookless cactus is anticipated as a result of project activities.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- The operator shall comply with all applicable requirements in the SOP (version: "Greater Monument Butte Green River Development Program", June 24, 2008). The operator shall also comply with applicable laws and regulations; with the lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized officer.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB

or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of

the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of

Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By
Branden Arnold Phone Number 435-401-0223
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 7/29/13 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 7/29/13 3:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-45431
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GREATER MON BUTTE M-24-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1226 FNL 1912 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 24 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43047514000000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 7/29/2013	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Ross # 29 spud and drilled 332' of 12 1/4" hole, P/U and run 7 jts of 8 5/8" casing set 306.47'KB Cement w/Pro Petro w/175 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17 yield. Returned 5bbls to pit, bump plug to 290psi, BLM and State were notified of spud via email.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 12, 2013		
NAME (PLEASE PRINT) Cherei Neilson	PHONE NUMBER 435 646-4883	TITLE Drilling Technician
SIGNATURE N/A	DATE 8/12/2013	

NEWFIELD**Casing****Conductor**

Legal Well Name GMBU M-24-8-17			Wellbore Name Original Hole		
API/UWI 4304751400	Surface Legal Location SE/NW Sec 24 T8S R17E	Field Name GMBU CTB9	Well Type Exploration	Well Configuration Type Slant	
Well RC 500292099	County Uintah	State/Province Utah	Spud Date 8/5/2013 21:30	Rig Release Date 8/9/2013 12:00	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB) 606		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	13	18	7/29/2013	7/29/2013

Wellhead			
Type	Install Date	Service	Comment

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description	Set Depth (ftKB)	Run Date	Set Tension (kips)
Conductor	18	7/29/2013	
Centralizers	Scratchers		

Casing Components												
Item Des	OD (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)	ID (in)
Conductor	14	36.75	H-40		1	5.00	13.0	18.0				13.500

NEWFIELD**Casing****Surface**

Legal Well Name GMBU M-24-8-17			Wellbore Name Original Hole		
API/UWI 4304751400	Surface Legal Location SE/NW Sec 24 T8S R17E	Field Name GMBU CTB9	Well Type Exploration	Well Configuration Type Slant	
Well RC 500292099	County Uintah	State/Province Utah	Spud Date 8/5/2013 21:30	Rig Release Date 8/9/2013 12:00	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB) 606		

Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Vertical	12 1/4	13	332	7/29/2013	7/29/2013
Conductor	14	13	18	7/29/2013	7/29/2013

Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description	Set Depth (ftKB)	Run Date	Set Tension (kips)
Surface	327	7/29/2013	
Centralizers	Scratchers		
3			

Casing Components												
Item Des	OD (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)	ID (in)
Casing JT	8 5/8	24.00	J-55		5	222.94	57.8	280.7				
Float Collar	8 5/8	24.00	j-55		1	1.00	280.7	281.7				
Casing JT	8 5/8	24.00	J-55		1	43.80	281.7	325.5				
Guide Shoe	8 5/8	24.00	J-55		1	1.50	325.5	327.0				

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By
Branden Arnold Phone Number 435-401-0223
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 7/29/13 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 7/29/13 3:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

RECEIVED
JUL 29 2013
DIV. OF OIL, GAS & MINING

Date/Time _____ AM ☐ PM ☐

Remarks _____

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Capstar 329
Submitted By Richard Hadlock Phone Number 970-361-3001
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

Rig Move Notice – Move drilling rig to new location.

Date/Time 8/5/2013 07:00 AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time 8/5/2013 16:00 AM ☐ PM ☐

Remarks _____

RECEIVED

AUG 04 2013

DIV. OF OIL, GAS & MINING

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Capstar 329
Submitted By Richard Hadlock Phone Number 970-361-3001
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

TD Notice – TD is the final drilling depth of hole.

Date/Time 8/8/2013 00:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 8/8/2013 15:30 AM ☐ PM ☒

RECEIVED

AUG 0 / 2013

DIV. OF OIL, GAS & MINING

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By
Branden Arnold Phone Number 435-401-0223
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 7/29/13 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
☐ Intermediate Casing
☐ Production Casing
☐ Liner
☐ Other

Date/Time 7/29/13 3:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
☐ BOPE test at intermediate casing point
☐ 30 day BOPE test
☐ Other

RECEIVED
JUL 29 2013
DIV. OF OIL, GAS & MINING

Date/Time _____ AM ☐ PM ☐

Remarks _____

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Capstar 329
Submitted By Richard Hadlock Phone Number 970-361-3001
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

Rig Move Notice – Move drilling rig to new location.

Date/Time 8/5/2013 07:00 AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time 8/5/2013 16:00 AM ☐ PM ☐

Remarks _____

RECEIVED

AUG 04 2013

DIV. OF OIL, GAS & MINING

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Capstar 329
Submitted By Richard Hadlock Phone Number 970-361-3001
Well Name/Number GMBU M-24-8-17
Qtr/Qtr SE/NW Section 24 Township 8S Range 17E
Lease Serial Number UTU-45431
API Number 43-047-51400

TD Notice – TD is the final drilling depth of hole.

Date/Time 8/8/2013 00:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 8/8/2013 15:30 AM ☐ PM ☒

RECEIVED

AUG 0 / 2013

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-45431
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GREATER MON BUTTE M-24-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1226 FNL 1912 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 24 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43047514000000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/6/2013	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above well was placed on production on 09/06/2013 at 16:00 hours.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 08, 2013		
NAME (PLEASE PRINT) Jennifer Peatross	PHONE NUMBER 435 646-4885	TITLE Production Technician
SIGNATURE N/A	DATE 10/7/2013	

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
 b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
 Other: _____

2. Name of Operator
 NEWFIELD PRODUCTION COMPANY

3. Address ROUTE #3 BOX 3630
 MYTON, UT 84052

3a. Phone No. (include area code)
 Ph: 435-646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 1226' FNL 1912' FWL (SE/NW, Lot #3) Sec 24, T8S, R17E (UTU-45431)

At top prod. interval reported below 1693' FNL 2610' FWL (SE/NW, Lot #3) Sec 24, T8S, R17E (UTU-45431)

2509' FSL 2380' FEL (NW/SE) Sec 24, T8S, R17E (UTU-45431)

At total depth

14. Date Spudded
 07/29/2103

15. Date T.D. Reached
 08/09/2013

16. Date Completed 09/04/2013
☐ D & A ☒ Ready to Prod.

17. Elevations (DF, RKB, RT, GL)*
 4995' GL 5008' KB

18. Total Depth: MD 6670'
 TVD 6543'

19. Plug Back T.D.: MD 6615'
 TVD

20. Depth Bridge Plug Set: MD
 TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
 DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? ☒ No ☐ Yes (Submit analysis)
 Was DST run? ☒ No ☐ Yes (Submit report)
 Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	327'		200 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6662'		300 Econocem		75'	
						450Expandacem			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@6276'	TA@6176'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River	4766'	6194'	4766' - 6194' MD	.34	52	
B)						
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
4766' - 6194' MD	Frac w/ 306500#s of 20/40 white sand in 3192 bbls of Lightning 17 fluid, in 4 stages.

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
9/6/13	9/16/13	24	→	83	71	27			2.5 x 1.75 x 24 RHAC
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press. SI	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (*Solid, used for fuel, vented, etc.*)**30. Summary of Porous Zones (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

**31. Formation (Log) Markers
GEOLOGICAL MARKERS**

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK	4264
				GARDEN GULCH 1	4451
				GARDEN GULCH 2	4577
				POINT 3	4863
				X MRKR	5084
				Y MRKR	5120
				DOUGLAS CREEK MRK	5263
				BI CARBONATE MRK	5552
				B LIMESTONE MRK	5714
				CASTLE PEAK	6104
				BASAL CARBONATE	6513
				WASATCH	6635

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (*please print*) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 10/02/2013

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 24 T8S R17E
M-24-8-17
Wellbore #1**

Design: Actual

End of Well Report

08 August, 2013





Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION Project: USGS Mylon SW (UT) Site: SECTION 24 T8S R17E Well: M-24-8-17 Wellbore: Wellbore #1 Design: Actual		Local Co-ordinate Reference: Well M-24-8-17 M-24-8-17 @ 5005.0ft (Capstar 329) M-24-8-17 @ 5005.0ft (Capstar 329) True Minimum Curvature EDM 2003.21 Single User Db	
Project: USGS Mylon SW (UT), DUCHESNE COUNTY, UT, USA Map System: US State Plane 1983 Geo Datum: North American Datum 1983 Map Zone: Utah Central Zone		System Datum: Mean Sea Level	
Site: SECTION 24 T8S R17E			
Site Position: From: Lat/Long 0.0 ft Position Uncertainty: 0.0 ft		Northing: 7,209,800.00 ft Easting: 2,072,800.00 ft Slot Radius: "	
		Latitude: 40° 6' 9.036 N Longitude: 109° 57' 14.911 W Grid Convergence: 0.99 °	
Well M-24-8-17, SHL LAT: 40° 06' 18.00, LONG: -109° 57' 26.86			
Well Position +N/-S 0.0 ft +E/-W 0.0 ft Position Uncertainty 0.0 ft		Northing: 7,210,690.82 ft Easting: 2,071,856.08 ft Wellhead Elevation: 5,005.0 ft Latitude: 40° 6' 18.000 N Longitude: 109° 57' 26.860 W Ground Level: 4,995.0 ft	
Wellbore Wellbore #1			
Magnetics		Field Strength (nT) 52,390	
Design Actual		Dip Angle (°) 65.88	
Audit Notes: 1.0		Declination (°) 11.37	
Version:		Sample Date 10/8/2010	
Vertical Section:		Phase: ACTUAL	
Depth From (TVD) (ft) 0.0		Tie On Depth: +N/-S (ft) 0.0 +E/-W (ft) 0.0	
Direction (°) 123.77			
Survey Program			
From (ft) 399.0		Date 8/8/2013	
To (ft) 6,870.0		Survey (Wellbore) Survey #1 (Wellbore #1)	
Tool Name MWD		Description MWD - Standard	



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well M-24-8-17
TVD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
MD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003 21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	0.0	0.00	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00
	399.0	0.80	153.30	399.0	2.4	-2.5	1.3	0.20	0.20	0.00
	430.0	0.80	151.90	430.0	2.8	-2.9	1.5	0.06	0.00	-4.52
	461.0	0.70	170.90	461.0	3.1	-3.3	1.6	0.86	-0.32	61.29
	491.0	0.80	162.10	491.0	3.4	-3.6	1.7	0.51	0.33	-29.33
	522.0	0.50	173.50	522.0	3.7	-4.0	1.8	1.05	-0.97	36.77
	552.0	0.70	160.30	552.0	3.9	-4.3	1.8	0.81	0.67	-44.00
	582.0	1.10	160.00	582.0	4.3	-4.7	2.0	1.33	1.33	-1.00
	612.0	1.80	161.30	612.0	4.9	-5.4	2.2	2.34	2.33	4.33
	643.0	2.30	153.40	642.9	5.8	-6.5	2.7	1.85	1.61	-25.48
	673.0	2.30	154.10	672.9	6.9	-7.5	3.2	0.09	0.00	2.33
	702.0	2.50	148.30	701.9	7.9	-8.6	3.8	1.08	0.69	-20.00
	733.0	3.00	145.00	732.9	9.3	-9.8	4.6	1.69	1.61	-10.65
	764.0	3.20	139.40	763.8	10.9	-11.2	5.6	1.17	0.65	-18.06
	795.0	3.30	136.50	794.8	12.6	-12.5	6.8	0.62	0.32	-9.35
	825.0	3.30	140.90	824.7	14.3	-13.8	8.0	0.84	0.00	14.67
	856.0	3.60	135.90	855.7	16.1	-15.1	9.2	1.37	0.97	-16.13
	887.0	4.00	135.80	886.6	18.1	-16.6	10.6	1.29	1.29	-0.32
	917.0	4.50	131.90	916.5	20.3	-18.2	12.2	1.92	1.67	-13.00
	949.0	5.10	132.00	948.4	22.9	-19.9	14.2	1.88	1.88	0.31
	979.0	5.30	132.00	978.3	25.6	-21.8	16.3	0.67	0.67	0.00
	1,009.0	5.60	132.10	1,008.1	28.4	-23.7	18.4	1.00	1.00	0.33
	1,040.0	6.10	131.30	1,039.0	31.6	-25.8	20.7	1.63	1.61	-2.58
	1,070.0	6.60	128.60	1,068.8	34.9	-27.9	23.3	1.94	1.67	-9.00
	1,114.0	7.40	125.50	1,112.5	40.2	-31.1	27.6	2.01	1.82	-7.05
	1,158.0	8.30	121.90	1,156.0	46.2	-34.4	32.6	2.33	2.05	-8.18
	1,202.0	8.80	121.20	1,199.6	52.8	-37.9	38.1	1.16	1.14	-1.59



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well M-24-8-17
TVD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
MD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	1,246.0	9.00	124.20	1,243.0	59.6	-41.5	43.9	1.15	0.45	6.82
	1,289.0	9.40	125.30	1,285.5	66.4	-45.5	49.5	1.02	0.93	2.56
	1,333.0	10.30	123.80	1,328.8	74.0	-49.7	55.7	2.13	2.05	-3.41
	1,377.0	11.20	123.50	1,372.1	82.2	-54.3	62.5	2.05	2.05	-0.68
	1,421.0	12.20	121.90	1,415.1	91.1	-59.1	70.1	2.39	2.27	-3.64
	1,464.0	12.70	121.70	1,457.1	100.3	-64.0	77.9	1.17	1.16	-0.47
	1,508.0	12.90	122.40	1,500.0	110.1	-69.2	86.2	0.58	0.45	1.59
	1,552.0	13.40	122.00	1,542.9	120.1	-74.5	94.7	1.16	1.14	-0.91
	1,596.0	13.50	122.00	1,585.7	130.3	-79.9	103.3	0.23	0.23	0.00
	1,640.0	13.60	121.80	1,628.4	140.6	-85.4	112.1	0.25	0.23	-0.45
	1,684.0	13.50	121.90	1,671.2	150.9	-90.8	120.8	0.23	-0.23	0.23
	1,727.0	13.50	121.90	1,713.0	161.0	-96.1	129.4	0.00	0.00	0.00
	1,771.0	13.50	122.20	1,755.8	171.2	-101.6	138.1	0.16	0.00	0.68
	1,815.0	13.60	121.10	1,799.6	181.5	-107.0	148.9	0.63	0.23	-2.50
	1,859.0	13.50	120.70	1,841.4	191.8	-112.3	155.7	0.31	-0.23	-0.91
	1,903.0	13.30	120.10	1,884.2	202.0	-117.4	164.5	0.55	-0.45	-1.36
	1,945.0	13.10	119.20	1,925.1	211.6	-122.2	172.8	0.68	-0.48	-2.14
	1,989.0	12.30	118.30	1,968.0	221.2	-126.8	181.3	1.87	-1.82	-2.05
	2,032.0	12.40	117.70	2,010.0	230.4	-131.1	189.4	0.38	0.23	-1.40
	2,076.0	12.50	117.50	2,053.0	239.8	-135.5	197.8	0.25	0.23	-0.45
	2,118.0	12.30	119.10	2,094.0	248.8	-139.8	205.8	0.95	-0.48	3.81
	2,162.0	12.20	119.00	2,137.0	258.1	-144.3	213.9	0.23	-0.23	-0.23
	2,206.0	12.30	118.50	2,180.0	267.4	-148.8	222.1	0.33	0.23	-1.14
	2,249.0	12.20	120.50	2,222.0	276.5	-153.3	230.1	1.01	-0.23	4.65
	2,293.0	11.70	122.10	2,265.0	285.6	-158.0	237.8	1.36	-1.14	3.64
	2,337.0	11.70	123.60	2,308.1	294.5	-162.9	245.3	0.69	0.00	3.41
	2,381.0	12.10	125.70	2,351.2	303.6	-168.0	252.8	1.34	0.91	4.77



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well M-24-8-17
TVD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
MD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	D Leg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	2,424.0	11.90	126.60	2,393.2	312.5	-173.3	260.0	0.64	-0.47	2.09
	2,468.0	12.30	126.60	2,436.3	321.7	-178.8	267.4	0.91	0.91	0.00
	2,512.0	12.30	127.90	2,479.3	331.1	-184.5	274.9	0.63	0.00	2.95
	2,555.0	12.50	127.70	2,521.3	340.3	-190.2	282.2	0.48	0.47	-0.47
	2,599.0	13.20	126.30	2,564.1	350.0	-196.0	290.0	1.74	1.59	-3.18
	2,642.0	13.40	125.70	2,606.0	359.9	-201.9	298.0	0.57	0.47	-1.40
	2,686.0	13.70	124.40	2,648.8	370.2	-207.8	306.4	0.97	0.68	-2.95
	2,730.0	13.90	122.80	2,691.5	380.7	-213.6	315.2	0.98	0.45	-3.64
	2,773.0	13.80	120.60	2,733.3	391.0	-219.0	323.9	1.25	-0.23	-5.12
	2,817.0	13.20	120.10	2,776.0	401.3	-224.2	332.8	1.39	-1.36	-1.14
	2,861.0	13.30	119.10	2,818.9	411.3	-229.2	341.6	0.57	0.23	-2.27
	2,905.0	13.50	120.20	2,861.7	421.5	-234.2	350.4	0.74	0.45	2.50
	2,948.0	13.00	121.70	2,903.5	431.3	-239.3	358.9	1.41	-1.16	3.49
	2,992.0	13.10	122.30	2,946.4	441.3	-244.5	367.3	0.38	0.23	1.36
	3,036.0	13.40	122.20	2,989.2	451.3	-249.9	375.8	0.68	0.68	-0.23
	3,080.0	13.70	121.90	3,032.0	461.6	-255.4	384.6	0.70	0.68	-0.68
	3,124.0	14.10	121.80	3,074.7	472.2	-261.0	393.6	0.91	0.91	-0.23
	3,167.0	14.00	121.50	3,116.4	482.6	-266.4	402.4	0.29	-0.23	-0.70
	3,211.0	13.00	120.00	3,159.2	492.9	-271.7	411.3	2.41	-2.27	-3.41
	3,255.0	12.00	118.80	3,202.2	502.4	-276.4	419.6	2.35	-2.27	-2.73
	3,299.0	11.20	119.30	3,245.3	511.2	-280.7	427.3	1.83	-1.82	1.14
	3,342.0	10.90	120.70	3,287.5	519.4	-284.8	434.4	0.94	-0.70	3.26
	3,385.0	10.60	121.00	3,329.7	527.4	-288.9	441.3	0.71	-0.70	0.70
	3,429.0	10.40	124.00	3,373.0	535.5	-293.2	448.1	1.32	-0.45	6.82
	3,473.0	10.70	127.30	3,416.2	543.5	-297.9	454.6	1.53	0.68	7.50
	3,515.0	11.50	128.40	3,457.4	551.6	-302.9	461.0	1.97	1.90	2.62
	3,559.0	12.60	129.50	3,500.5	560.7	-308.6	468.1	2.55	2.50	2.50



Payzone Directional

End of Well Report



Company:	NEWFIELD EXPLORATION	Local Co-ordinate Reference:	Well M-24-8-17
Project:	USGS Myton SW (UT)	TVD Reference:	M-24-8-17 @ 5005.0ft (Capstar 329)
Site:	SECTION 24 T8S R17E	MD Reference:	M-24-8-17 @ 5005.0ft (Capstar 329)
Well:	M-24-8-17	North Reference:	True
Wellbore:	Wellbore #1	Survey Calculation Method:	Minimum Curvature
Design:	Actual	Database:	EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	3,603.0	12.90	129.60	3,543.4	570.4	-314.8	475.6	0.68	0.68	0.23
	3,647.0	12.20	128.60	3,586.3	579.9	-320.9	483.1	1.67	-1.59	-2.27
	3,690.0	12.00	125.40	3,628.4	588.9	-326.3	490.2	1.63	-0.47	-7.44
	3,734.0	12.70	125.10	3,671.4	598.3	-331.7	497.9	1.60	1.59	-0.68
	3,778.0	13.40	125.00	3,714.2	608.2	-337.4	506.1	1.59	1.59	-0.23
	3,821.0	13.60	125.50	3,756.0	618.3	-343.2	514.3	0.54	0.47	1.16
	3,866.0	13.70	123.60	3,799.8	628.9	-349.2	523.0	1.02	0.22	-4.22
	3,908.0	13.50	124.40	3,840.6	638.8	-354.8	531.2	0.65	-0.48	1.90
	3,952.0	13.60	122.80	3,883.4	649.1	-360.5	539.8	0.88	0.23	-3.64
	3,996.0	13.70	124.20	3,926.1	659.5	-366.2	548.4	0.78	0.23	3.18
	4,039.0	14.30	124.90	3,967.8	669.9	-372.1	557.0	1.45	1.40	1.63
	4,083.0	14.70	124.00	4,010.4	680.9	-378.3	566.1	1.04	0.91	-2.05
	4,127.0	14.70	124.90	4,053.0	692.0	-384.6	575.3	0.52	0.00	2.05
	4,171.0	14.10	124.10	4,095.6	703.0	-390.8	584.3	1.44	-1.36	-1.82
	4,214.0	13.40	124.20	4,137.4	713.2	-396.6	592.8	1.63	-1.63	0.23
	4,257.0	13.00	124.80	4,179.2	723.0	-402.1	600.9	0.98	-0.93	1.40
	4,301.0	12.60	125.80	4,222.2	732.8	-407.8	608.8	1.04	-0.91	2.27
	4,344.0	13.00	127.20	4,264.1	742.3	-413.4	616.5	1.18	0.93	3.26
	4,387.0	13.40	126.40	4,305.9	752.1	-419.3	624.3	1.02	0.93	-1.86
	4,430.0	13.60	124.50	4,347.8	762.1	-425.1	632.5	1.13	0.47	-4.42
	4,474.0	13.70	123.90	4,390.5	772.5	-431.0	641.1	0.39	0.23	-1.36
	4,518.0	13.60	121.80	4,433.3	782.9	-436.6	649.8	1.15	-0.23	-4.77
	4,562.0	13.10	120.90	4,476.1	793.0	-441.9	658.5	1.23	-1.14	-2.05
	4,605.0	12.80	119.50	4,518.0	802.6	-446.7	666.8	1.01	-0.70	-3.26
	4,649.0	12.40	121.80	4,560.9	812.2	-451.6	675.1	1.46	-0.91	5.23
	4,693.0	12.30	122.90	4,603.9	821.6	-456.7	683.0	0.58	-0.23	2.50
	4,737.0	12.00	126.00	4,646.9	830.9	-461.9	690.7	1.63	-0.68	7.05



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well M-24-8-17
TVD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
MD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	4,781.0	11.40	127.20	4,690.0	839.8	-467.2	697.8	1.47	-1.36	2.73
	4,824.0	11.90	129.20	4,732.1	848.5	-472.6	704.7	1.49	1.16	4.65
	4,868.0	12.20	129.80	4,775.2	857.6	-478.4	711.7	0.74	0.68	1.36
	4,911.0	11.70	130.40	4,817.2	866.4	-484.2	718.6	1.20	-1.16	1.40
	4,955.0	11.60	128.00	4,860.3	875.3	-489.8	725.4	1.12	-0.23	-5.45
	4,997.0	11.90	129.00	4,901.4	883.8	-495.1	732.1	0.86	0.71	2.38
	5,041.0	12.10	128.40	4,944.5	892.9	-500.8	739.3	0.54	0.45	-1.36
	5,085.0	12.30	128.20	4,987.5	902.2	-506.6	746.6	0.46	0.45	-0.45
	5,129.0	12.40	127.20	5,030.5	911.6	-512.3	754.0	0.54	0.23	-2.27
	5,143.1	12.43	126.80	5,044.3	914.6	-514.2	756.4	0.65	0.23	-2.81
M-24-8-17 TGT										
	5,172.0	12.50	126.00	5,072.5	920.8	-517.9	761.5	0.65	0.23	-2.78
	5,214.0	12.60	125.20	5,113.5	930.0	-523.2	768.9	0.48	0.24	-1.90
	5,258.0	12.30	124.20	5,156.4	939.4	-528.6	776.7	0.84	-0.68	-2.27
	5,302.0	12.00	123.80	5,199.4	948.7	-533.8	784.4	0.71	-0.68	-0.91
	5,344.0	12.10	122.60	5,240.5	957.5	-538.6	791.7	0.64	0.24	-2.86
	5,388.0	12.10	121.10	5,283.5	966.7	-543.4	799.5	0.71	0.00	-3.41
	5,432.0	11.90	121.30	5,326.6	975.8	-548.2	807.3	0.46	-0.45	0.45
	5,476.0	11.80	121.50	5,369.6	984.9	-552.9	815.1	0.25	-0.23	0.45
	5,520.0	12.20	121.30	5,412.7	994.0	-557.6	822.9	0.91	0.91	-0.45
	5,563.0	12.40	120.40	5,454.7	1,003.1	-562.3	830.7	0.64	0.47	-2.09
	5,607.0	11.80	120.80	5,497.7	1,012.4	-567.0	838.7	1.38	-1.36	0.91
	5,651.0	11.80	120.60	5,540.8	1,021.3	-571.6	846.4	0.09	0.00	-0.45
	5,694.0	12.10	121.10	5,582.8	1,030.2	-576.2	854.1	0.74	0.70	1.16
	5,737.0	11.90	121.00	5,624.9	1,039.2	-580.8	861.7	0.47	-0.47	-0.23
	5,779.0	12.00	120.50	5,666.0	1,047.8	-585.2	869.2	0.34	0.24	-1.19
	5,822.0	11.90	118.90	5,708.1	1,056.7	-589.7	876.9	0.80	-0.23	-3.72



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 24 T8S R17E
Well: M-24-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
MD Reference: M-24-8-17 @ 5005.0ft (Capstar 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	5,865.0	11.50	118.30	5,750.2	1,065.4	-593.8	884.6	0.97	-0.93	-1.40
	5,909.0	11.10	117.50	5,793.3	1,074.0	-597.9	892.2	0.98	-0.91	-1.82
	5,952.0	10.80	120.50	5,835.5	1,082.1	-601.8	899.3	1.50	-0.70	6.98
	5,996.0	10.60	125.00	5,878.8	1,090.3	-606.2	906.2	1.95	-0.45	10.23
	6,039.0	10.20	127.30	5,921.1	1,098.0	-610.8	912.5	1.34	-0.93	5.35
	6,083.0	10.10	128.00	5,964.4	1,105.8	-615.5	918.6	0.36	-0.23	1.59
	6,126.0	10.50	128.50	6,006.7	1,113.4	-620.3	924.6	0.95	0.93	1.16
	6,170.0	11.30	130.00	6,049.9	1,121.7	-625.6	931.1	1.93	1.82	3.41
	6,213.0	11.00	132.40	6,092.1	1,130.0	-631.1	937.3	1.29	-0.70	5.58
	6,257.0	10.90	133.70	6,135.3	1,138.2	-636.8	943.5	0.61	-0.23	2.95
	6,300.0	10.60	134.50	6,177.5	1,146.1	-642.3	949.2	0.78	-0.70	1.86
	6,343.0	10.00	135.20	6,219.8	1,153.7	-647.8	954.7	1.43	-1.40	1.63
	6,386.0	9.40	135.00	6,262.2	1,160.8	-652.9	959.8	1.40	-1.40	-0.47
	6,430.0	8.70	137.20	6,305.7	1,167.5	-657.9	964.6	1.77	-1.59	5.00
	6,474.0	8.20	137.90	6,349.2	1,173.8	-662.6	968.9	1.16	-1.14	1.59
	6,518.0	8.10	136.50	6,392.7	1,179.9	-667.2	973.2	0.51	-0.23	-3.18
	6,561.0	7.80	137.20	6,435.3	1,185.7	-671.6	977.3	0.73	-0.70	1.63
	6,616.0	7.30	138.70	6,489.9	1,192.7	-676.9	982.1	0.98	-0.91	2.73
	6,670.0	7.30	138.70	6,543.4	1,199.3	-682.1	986.6	0.00	0.00	0.00

Checked By: _____



Approved By: _____

Date: _____



Project: USGS Myton SW (UT)
 Site: SECTION 24 T8S R17E
 Well: M-24-8-17
 Wellbore: Wellbore #1
 Design: Actual

Azimuths to True North
 Magnetic North: 11.37°
 Magnetic Field
 Strength: 52389.8nT
 Dip Angle: 65.88°
 Date: 10/8/2010
 Model: IGRF2010



Design: Actual (M-24-8-17/Wellbore #1)

Created By: Sarah Webb Date: 16:14, August 08 2013

THIS SURVEY IS CORRECT TO THE BEST OF
 MY KNOWLEDGE AND IS SUPPORTED
 BY ACTUAL FIELD DATA

NEWFIELD



Well Name: GMBU M-24-8-17

Summary Rig Activity

Job Category		Job Start Date		Job End Date	
Daily Operations					
Report Start Date	Report End Date	24hr Activity Summary			
8/27/2013	8/28/2013	Ran CBL, CCL, Gamma Ray with Perforators, Pressure tested Frac Stack, and Perforated 1st stage			
Start Time		End Time	Comment		
	00:00	11:30			
Start Time		End Time	Comment		
	11:30	13:30	Ran CBL, CCL, and Gamma Ray Log		
Start Time		End Time	Comment		
	13:30	16:00	Pressure tested Frac Stack and casing		
Start Time		End Time	Comment		
	16:00	17:00	Perforated 1st Stage		
Start Time		End Time	Comment		
	17:00	00:00			
Report Start Date	Report End Date	24hr Activity Summary			
8/28/2013	8/29/2013	Frac and perf all 4 stages. Flow back well.			
Start Time		End Time	Comment		
	00:00	09:00			
Start Time		End Time	Comment		
	09:00	13:30	MIRU Halliburton, Pressure Test, Safety Meeting		
Start Time		End Time	Comment		
	13:30	14:30	Pump and Frac 1st stage		
Start Time		End Time	Comment		
	14:30	15:15	Ran in w/ WL and perf'd 2nd stage		
Start Time		End Time	Comment		
	15:15	16:00	Pump and Frac 2nd stage		
Start Time		End Time	Comment		
	16:00	16:30	Ran in w/ WL and perf'd 3rd Stage		
Start Time		End Time	Comment		
	16:30	17:00	Pump and Frac 3rd stage		
Start Time		End Time	Comment		
	17:00	17:45	Ran in w/ WL and perf'd 4th Stage		
Start Time		End Time	Comment		
	17:45	19:15	Wait on sand haulers to blow off enough sand in Movers to finish last stage (30 mins) and then pump and frac 4th stage		
Start Time		End Time	Comment		
	19:15	00:00			
Report Start Date	Report End Date	24hr Activity Summary			
8/29/2013	8/30/2013	Set Kill Plug and shut in well			
Start Time		End Time	Comment		
	00:00	07:00			
Start Time		End Time	Comment		
	07:00	09:00	Set Kill Plug and shut in well		
Start Time		End Time	Comment		
	09:00	00:00			
Report Start Date	Report End Date	24hr Activity Summary			
8/30/2013	8/31/2013	psi test/Drillout plugs			
Start Time		End Time	Comment		
	00:00	06:00			
Start Time		End Time	Comment		
	06:00	07:00			

NEWFIELD



Well Name: GMBU M-24-8-17

Summary Rig Activity

Start Time	07:00	End Time	08:00	Comment
Start Time	08:00	End Time	10:00	SIRU/Derrick inspection
Start Time	10:00	End Time	11:00	RU workflow. RU tbg equip., RU lifting cylinder, unload, prep & tally 215 jts 2 7/8" J-55 tbg. Build pump & return lines
Start Time	11:00	End Time	14:00	S&S finish up testing stack
Start Time	14:00	End Time	14:30	PU & RIH w/4 3/4" mill, x-o, 141 jts, tag fill 7 jts high @ 4430
Start Time	14:30	End Time	19:00	RU pwr swvl, strip on wash, rubber, break circ
Start Time	19:00	End Time	20:00	Comment
Start Time	20:00	End Time	21:00	CLEAN OUT FILL DWN TO KILL PLUG @ 4650, DRILL OUT KILL PLUG 20 MIN, (NO PRESSURE) POWER SWIVEL NOT SPINNING VERY WELL, SWIVEL IN 7 JNTS TAGGING FIRST PLUG @ 4895 JN 155 (NO FILL), NO ADDITIONAL PRESSURE, HANG SWIVEL BACK PU 10 JNTS TAGGING 100 FT OF FILL ON SECOND PLUG, CLEAN OUT FILL, DRILL OUT PLUG @ 5300, 30 MIN, SWIVEL SPINNING SLOWER, SWIVEL N 7 JNTS TAGGING 40 FT OF FILL ON LAST PLUG CLEAN OUT FILL DRILL UP PLUG @ 5560 JNT 176 (35 MIN), HANG SWIVEL BACK, PU 16 JNTS, TAGGING 600 FT OF FILL, CLEAN OUT 6 JNTS OF FILL BEFORE SWIVEL WOULDNT SPIN ANYMORE, RACK OUT POWER SWIVEL
Start Time	21:00	End Time	00:00	Comment
Start Time	00:00	End Time	06:00	roll hole clean, 150 bbls, LD 6 jts, SWIFN
Start Time	06:00	End Time	07:00	Comment
Start Time	07:00	End Time	08:30	Comment
Start Time	08:30	End Time	11:30	200# on tbg, 400# on csg, open up tbg to flow, flowing 75 bbls before dieing off
Start Time	11:30	End Time	13:00	RU pwr swvl, RIH tagging new ft of fill, clean out 330' of fill dwn to PBTD @ 6615'
Start Time	13:00	End Time	14:30	Circ, 200 bbls before returns were clear
Start Time	14:30	End Time	16:00	rack out swvl, LD 17 jts, POOH w/198 jts, x-o, mill
Start Time	16:00	End Time	17:00	RIH w/NC, 2 jts, SN, 1 jt, TAC, 195 jts, adding 4' sub to string, setting TAC from workflow, w/18000# pulled into it
Start Time	17:00	End Time		RD workflow, ND BOP, ND blind ram, remove 4' sub from well, land well, NU WH, 13' kb, 195 jts, TAC @ 6176.44', 1 jt, SN @ 6210.95', 2 jts, NC, EOT @ 6276.03'

 Report Start Date 9/3/2013
 Report End Date 9/4/2013
 24hr Activity Summary c/o to PBTD, rt tbg/SIH w/rods

NEWFIELD



Well Name: GMBU M-24-8-17

Summary Rig Activity

Start Time	17:00	End Time	19:00	Comment
Start Time	19:00	End Time	00:00	Comment
Report Start Date	9/4/2013	Report End Date	9/5/2013	24hr Activity Summary
Start Time	00:00	End Time	06:00	Comment
Start Time	06:00	End Time	07:00	Comment
Start Time	07:00	End Time	08:00	Comment
Start Time	08:00	End Time	10:00	Comment
Start Time	10:00	End Time	11:00	Comment
Start Time	11:00	End Time	12:00	Comment
Start Time	12:00	End Time	13:00	Comment
Start Time	13:00	End Time	00:00	Comment

Comment
x-o to rod equip. PU & prime new Central Hydraulics pump. 2.5x1.75x24', PU 30 7/8" 8pers, 133 3/4" 4pers, hang
polish rod for night, SWIFN

Comment

Report Start Date 9/4/2013 Report End Date 9/5/2013 24hr Activity Summary
Finish RIH w/rods & pump

Comment

Comment

Comment

Comment
350# on csg, 50# on tbgr. flush well w/20 bbls wtr

Comment

Comment
LD polish rod. PU 87 7/8" 4pers, space out w/8', 6', 4', & 2' 7/8" ponies, PU 30"x1.5" polish rod

Comment

Comment
Newfield mechanic pulled onto location, said he would have units started shortly to roll

Comment

Comment
Mechanic couldnt get unit started, bridaled head, hung head, NU unit, stroke up to 800 psi (good)

Comment

Comment
rig equipment down

Comment

Comment
PWOP

RECEIVED: Oct. 03, 2013